

工 事 概 要

建設改良費（更新）

種 別	形 質	単 位	当 初	変 更
布設工	D I P φ 2 0 0	m	7 0	7 1
	D I P φ 1 0 0	m	1 1	8
	H I V P φ 7 5	m	3	7
設置工	仕切弁 φ 2 0 0	箇所	1	1
	仕切弁 φ 1 0 0	箇所	3	3
	仕切弁 φ 7 5	箇所	1	1
撤去工	C I P φ 2 0 0	m	7 0	7 0
	D I P φ 7 5	m	1 7	1 7
給水管接合替工		箇所	1 1	1 1
仮設給水替工		式	1	1
付帯工		式	1	1

(030010-1)

直接工事費内訳書

工種：開削工事及び小口径推進工事

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
φ200本管工事(更新)							(1,993,581)	
							3,267,502	
							(1,907,441)	
							3,175,913	
材料費					1	(1,912,288)	(1,912,288)	
							1,995,358	1,995,358
土工				式	1	(1,824,868)	(1,824,868)	
							1,907,938	1,907,938
					1	934,823	934,823	
管工				式	1	934,823	934,823	
					1	(81,293)	(81,293)	
							337,321	337,321
管工				式	1	(82,573)	(82,573)	
							333,152	333,152
φ100本管工事(更新)							(710,326)	
							1,323,198	
							(750,527)	
							1,374,823	
材料費					1	(699,556)	(699,556)	
							926,236	926,236
土工				式	1	(741,756)	(741,756)	
							980,286	980,286
					1	269,219	269,219	
管工				式	1	269,219	269,219	
					1	(10,770)	(10,770)	
							127,743	127,743
管工				式	1	(8,771)	(8,771)	
							125,318	125,318
給水管接合替工事(更新)							(461,403)	
							932,913	
							(461,403)	
							932,913	
土工					1	250,274	250,274	
				式	1	250,274	250,274	

(030010-1)

直接工事費内訳書

工種：開削工事及び小口径推進工事

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
					1	(461,403) 682,639	(461,403) 682,639	
	管工			式	1	(461,403) 682,639	(461,403) 682,639	
							(420,091) 2,425,077	
仮設給水替工事(更新)							(420,091) 2,425,077	
					1	(377,708) 377,708	(377,708) 377,708	
	材料費			式	1	(377,708) 377,708	(377,708) 377,708	
					1	645,704	645,704	
	土工			式	1	645,704	645,704	
					1	(42,383) 1,401,665	(42,383) 1,401,665	
	管工			式	1	(42,383) 1,401,665	(42,383) 1,401,665	
							78,489	
φ200本管撤去工事(更新)							78,489	
					1	78,489	78,489	
	管工			式	1	78,489	78,489	
							208,750	
φ75本管撤去工事(更新)							208,750	
					1	196,962	196,962	
	土工			式	1	196,962	196,962	
					1	11,788	11,788	
	管工			式	1	11,788	11,788	

(030010-1)

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事

費 目	工 種	種 別	細別／規格	単 位	数 量	単 価	金 額	摘 要
直接工事費					1		(3,585,401)	
				式	1		10,894,298	
共通仮設費					1		(3,539,462)	
				式	1		10,902,733	
					1		2,102,248	
				式	1		2,106,248	
共通仮設費率計算額					1		1,339,000	
				式	1		1,343,000	
共通仮設費 積上額計					1		763,248	
				式	1		763,248	
		運搬費			1		4,368	
				式	1		4,368	
			運搬費		1		4,368	
				式	1		4,368	
		安全費			1		673,200	
				式	1		673,200	
			安全費		1		673,200	
				式	1		673,200	
		技術管理費			1		85,680	
				式	1		85,680	
			土質試験 土質区分判定のための調査試験		1		85,680	
				式	1		85,680	

(030010-1)

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事

費 目	工 種	種 別	細別／規格	単 位	数 量	単 価	金 額	摘 要
純工事費					1		12,996,546	
				式	1		13,008,981	
現場管理費					1		3,113,000	
				式	1		3,121,000	
現場管理費率計算額					1		3,113,000	
				式	1		3,121,000	
工事原価					1		16,109,546	
				式	1		16,129,981	
一般管理費等					1		2,830,454	
				式	1		2,830,019	
一般管理費率計算額					1		2,831,000	
				式	1		2,833,000	
契約保証費					1		6,299	
				式	1		6,306	
工事価格					1		18,940,000	
				式	1		18,960,000	
消費税相当額					1		1,515,200	
				式	1		1,516,800	
本工事費					1		20,455,200	
				式	1		20,476,800	