

工 事 概 要

建設改良費（鉛管）

種 別	形 質	単 位	当 初	変 更
布設工	D I P φ 1 5 0	m	2 3 2 . 4	2 3 2 . 4
	D I P φ 1 0 0	m	4 7 . 8	1 1 6 . 5
	D I P φ 7 5	m	4 . 6	3 . 1
	P E φ 7 5	m	1 2 7 . 8	5 9 . 2
	H I V P φ 7 5	m	1 . 9	1 . 9
設置工	仕切弁 φ 1 5 0	箇所	9	9
	仕切弁 φ 1 0 0	箇所	1	2
	仕切弁 φ 7 5	箇所	4	3
	消火栓 φ 7 5	箇所	2	2
撤去工	C I P φ 1 5 0	m	1 7 0	1 7 0
	H I V P φ 7 5	m	8	8
	H I V P φ 5 0	m	3 6	3 6
	H I V P φ 4 0	m	2 5	2 5
給水管接合替工		箇所	4 1	4 1
仮設給水替工		式	1	1
付帯工		式	1	1

直接工事費内訳書

工種：開削工事及び小口径推進工事

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
φ150本管工事（鉛管）							(5,569,000)	
							10,499,183	
	材料費				1	(5,569,000) 6,199,200	(5,569,000) 6,199,200	
				式	1	(5,569,000) 6,199,200	(5,569,000) 6,199,200	
	土工				1	3,209,119	3,209,119	
				式	1	3,209,119	3,209,119	
	管工				1	1,090,864	1,090,864	
				式	1	1,090,864	1,090,864	
φ100本管工事（鉛管）							(625,647)	
							1,473,912	
	材料費				1	(625,647) 702,917	(625,647) 702,917	
				式	1	(1,627,307) 1,830,617	(1,627,307) 1,830,617	
	土工				1	536,071	536,071	
				式	1	1,339,386	1,339,386	
	管工				1	234,924	234,924	
				式	1	519,849	519,849	
φ75本管工事（鉛管）							(810,730)	
							3,020,903	
	材料費				1	(810,730) 999,790	(810,730) 999,790	
				式	1	(391,110) 454,130	(391,110) 454,130	

直接工事費内訳書

工種：開削工事及び小口径推進工事

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
					1	1,759,519	1,759,519	
	土工			式	1	873,256	873,256	
					1	261,594	261,594	
	管工			式	1	121,268	121,268	
φ150消火栓設置工事(鉛管)							(390,125)	
							702,057	
							(390,125)	
							702,057	
材料費					1	(390,125)	(390,125)	
				式	1	668,185	668,185	
							(390,125)	
				式	1	668,185	668,185	
					1	33,872	33,872	
	管工			式	1	33,872	33,872	
給水管接合替工事(鉛管)							(1,955,888)	
							3,880,838	
							(1,955,068)	
							3,882,309	
材料費					1	(5,185)	(5,185)	
				式	1	5,185	5,185	
							(5,185)	
				式	1	5,185	5,185	
					1	825,645	825,645	
	土工			式	1	825,645	825,645	
					1	(1,950,703)	(1,950,703)	
							3,050,008	
							(1,949,883)	
	管工			式	1	3,051,479	3,051,479	
仮設給水替工事(鉛管)							(711,539)	
							5,041,828	
							(711,539)	
							5,041,828	

直接工事費内訳書

工種：開削工事及び小口径推進工事

費目	工種	種別	細別／規格	単位	数量	単価	金額	摘要
	材料費				1	(526,340) 641,780	(526,340) 641,780	
				式	1	(526,340) 641,780	(526,340) 641,780	
	土工				1	1,635,587	1,635,587	
				式	1	1,635,587	1,635,587	
	管工				1	(185,199) 2,764,461	(185,199) 2,764,461	
				式	1	(185,199) 2,764,461	(185,199) 2,764,461	
φ 150本管撤去工事 (鉛管)							108,371	
							108,371	
	管工				1	108,371	108,371	
				式	1	108,371	108,371	
φ 75本管撤去工事 (鉛管)							7,256	
							7,256	
	管工				1	7,256	7,256	
				式	1	7,256	7,256	
φ 50本管撤去工事 (鉛管)							11,699	
							11,699	
	管工				1	11,699	11,699	
				式	1	11,699	11,699	
φ 40本管撤去工事 (鉛管)							6,502	
							6,502	

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事

費 目	工 種	種 別	細別／規格	単 位	数 量	単 価	金 額	摘 要
直接工事費					1		(10,062,929) 36,110,000	
				式	1		(10,644,149) 36,721,862	
共通仮設費					1		3,815,616	
				式	1		3,850,616	
					1		3,723,000	
				式	1		3,758,000	
	共通仮設費率計算額				1		92,616	
				式	1		92,616	
	共通仮設費 積上額計				1		6,936	
				式	1		6,936	
		運搬費			1		6,936	
				式	1		6,936	
			仮設材運搬		1		6,936	
				式	1		6,936	
		技術管理費			1		85,680	
				式	1		85,680	
			土質試験 <small>土質区分判定のための調査試験/2試料</small>		1		85,680	
				式	1		85,680	
純工事費					1		39,925,616	
				式	1		40,572,478	
	現場管理費				1		8,876,000	
				式	1		8,965,000	

