

工 事 概 要

建設改良費（依頼 南中振 2丁目）

種 別	形 質	単 位	当 初	変 更
布設工	PE φ 75	m	46.1	47.9
設置工	仕切弁 φ 75	箇所	2	2
	消火栓 φ 75	箇所	1	1
撤去工	CIP φ 75	m	20	20
	DIP φ 75	m	4	4
	HIVP φ 75	m	23	23
	VLP φ 80	m	4	4
給水管接合替工		箇所	3	2
仮設給水替工		式	1	1

建設改良費（更新）

種 別	形 質	単 位	当 初	
布設工	PE φ 75	m	22.5	20.7
設置工	消火栓 φ 75	箇所	1	1
撤去工	HIVP φ 75	m	23	23
給水管接合替工		箇所	10	11
仮設給水替工		式	1	1

建設改良費（依頼 南中振 1丁目）

布設工	PP φ 40	m	7.0	7.0
撤去工	PP φ 40	m	6	6
給水管接合替工		箇所	1	1

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
φ75本管工事（依頼）							(757,184)	
							1,575,488	
φ75本管工事（依頼）							(777,504)	
							1,632,960	
	材料費				1	(757,184)	(757,184)	
						901,734	901,734	
				式	1	(777,504)	(777,504)	
						929,404	929,404	
	土工				1	470,281	470,281	
						491,888	491,888	
	管工				1	203,473	203,473	
						211,668	211,668	
φ75消火栓設置工事（依頼）							(198,792)	
							370,116	
φ75消火栓設置工事（依頼）							(186,492)	
							357,816	
	材料費				1	(198,792)	(198,792)	
						355,682	355,682	
				式	1	(186,492)	(186,492)	
						343,382	343,382	
	管工				1	14,434	14,434	
						14,434	14,434	
給水管接合替工事（依頼）							(117,283)	
							236,102	
給水管接合替工事（依頼）							(69,623)	
							144,103	
	土工				1	32,952	32,952	
						32,952	32,952	
	管工				1	(117,283)	(117,283)	
						203,150	203,150	
				式	1	(69,623)	(69,623)	
						111,151	111,151	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
仮設給水替工事（依頼）							(348,122)	
							792,556	
							(348,122)	
							792,556	
	材料費				1	(236,000)	(236,000)	
						299,300	299,300	
				式	1	(236,000)	(236,000)	
						299,300	299,300	
	土工				1	94,634	94,634	
				式	1	94,634	94,634	
	管工				1	(112,122)	(112,122)	
						398,622	398,622	
				式	1	(112,122)	(112,122)	
						398,622	398,622	
φ75本管撤去工事（依頼）							(12,980)	
							544,770	
							(12,980)	
							530,053	
	材料費				1	(12,980)	(12,980)	
						12,980	12,980	
				式	1	(12,980)	(12,980)	
						12,980	12,980	
	土工				1	485,342	485,342	
				式	1	473,053	473,053	
	管工				1	57,129	57,129	
				式	1	54,701	54,701	
	現場発生品				1	-10,681	-10,681	
				式	1	-10,681	-10,681	
仮設工（依頼）							314,600	
							281,700	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
					1	314,600	314,600	
	交通管理工			式	1	281,700	281,700	
φ75本管工事(更新)							(59,620)	
							293,244	
							(45,200)	
							257,713	
					1	(59,620)	(59,620)	
	材料費			式	1	(45,200)	(45,200)	
							45,200	
					1	197,712	197,712	
	土工			式	1	181,236	181,236	
					1	35,912	35,912	
	管工			式	1	31,277	31,277	
φ75消火栓設置工事(更新)							(185,867)	
							357,191	
							(185,867)	
							357,191	
					1	(185,867)	(185,867)	
	材料費			式	1	(185,867)	(185,867)	
							342,757	
					1	14,434	14,434	
	管工			式	1	14,434	14,434	
給水管接合替工事(更新)							(377,995)	
							771,299	
							(554,610)	
							956,582	
					1	98,856	98,856	
	土工			式	1	82,380	82,380	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
	管工				1	(377,995) 672,443	(377,995) 672,443	
				式	1	(554,610) 874,202	(554,610) 874,202	
仮設給水替工事 (更新)							(137,013) 510,645	
							(137,013) 510,645	
	土工				1	115,332	115,332	
				式	1	115,332	115,332	
	管工				1	(137,013) 395,313	(137,013) 395,313	
				式	1	(137,013) 395,313	(137,013) 395,313	
φ75本管撤去工事 (更新)							9,329	
							9,329	
	管工				1	9,329	9,329	
				式	1	9,329	9,329	
仮設工 (更新)							152,400	
							152,400	
	交通管理工				1	152,400	152,400	
				式	1	152,400	152,400	
φ40本管工事 (依頼 南1)							(49,833) 198,772	
							(49,833) 198,772	
	材料費				1	(49,833) 59,854	(49,833) 59,854	
				式	1	(49,833) 59,854	(49,833) 59,854	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
					1	109,246	109,246	
	土工			式	1	109,246	109,246	
					1	29,672	29,672	
	管工			式	1	29,672	29,672	
							(10,582)	
給水管接合替工事 (依頼 南1)							50,099	
							(10,582)	
							50,099	
					1	22,227	22,227	
	土工			式	1	22,227	22,227	
					1	(10,582) 27,872	(10,582) 27,872	
	管工			式	1	(10,582) 27,872	(10,582) 27,872	
							87,473	
φ40本管撤去工事 (依頼 南1)							87,473	
					1	73,179	73,179	
	土工			式	1	73,179	73,179	
					1	14,294	14,294	
	管工			式	1	14,294	14,294	
							76,200	
仮設工 (依頼 南1)							76,200	
					1	76,200	76,200	
	交通管理工			式	1	76,200	76,200	

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事等

費 目	工 種	種 別	細別／規格	単 位	数 量	単 価	金 額	摘 要
直接工事費					1		(2,255,271)	
				式	1		6,340,284	
共通仮設費					1		(2,377,826)	
				式	1		6,395,592	
共通仮設費					1		881,490	
				式	1		881,490	
	共通仮設費率計算額				1		802,000	
				式	1		802,000	
	共通仮設費 積上額計				1		79,490	
				式	1		79,490	
		運搬費			1		696	
				式	1		696	
			仮設材運搬費		1		696	
				式	1		696	
		準備費			1		78,794	
				式	1		78,794	
			試験掘工		1		78,794	
				式	1		78,794	
純工事費					1		7,221,774	
				式	1		7,277,082	
	現場管理費				1		2,448,000	
				式	1		2,446,000	

