

工 事 概 要

建設改良費（配水支管）

種 別	形 質	単 位	第 1 回 変 更	第 2 回 変 更
布設工	PE φ 1 5 0	m	2 8 9 . 3	2 8 9 . 3
	PE φ 1 0 0	m	3 2 2 . 5	3 2 2 . 5
	D I P φ 7 5	m	8 0 . 8	8 0 . 8
	PE φ 7 5	m	1 7 . 9	2 3 . 5
	PE φ 5 0	m	7 0 . 0	6 5 . 3
設置工	仕切弁 φ 1 5 0	箇所	3	3
	仕切弁 φ 1 0 0	箇所	5	5
	仕切弁 φ 7 5	箇所	3	3
	仕切弁 φ 5 0	箇所	1	1
	消火栓 φ 7 5	箇所	5	5
撤去工	C I P φ 1 5 0	m	2 5 7	2 5 7
	C I P φ 1 0 0	m	3 2 9	3 2 9
	C I P φ 7 5	m	1 3 0	1 3 0
	V P φ 5 0	m	7 6	7 6
給水管接合替工		箇所	7 3	7 4
仮設給水替工		式	1	1
付帯工		式	1	1

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
φ150本管工事（配水支管）							(3,243,740)	
							8,737,600	
φ150本管工事（配水支管）							(3,243,740)	
							8,624,539	
材料費					1	(3,243,740)	(3,243,740)	
							3,482,060	3,482,060
土工				式	1	(3,243,740)	(3,243,740)	
							3,482,060	3,482,060
					1	4,245,959	4,245,959	
管工				式	1	4,132,898	4,132,898	
					1	1,009,581	1,009,581	
φ100本管工事（配水支管）							(2,000,232)	
							7,571,739	
φ100本管工事（配水支管）							(2,013,162)	
							7,581,175	
材料費					1	(2,000,232)	(2,000,232)	
							2,397,432	2,397,432
土工				式	1	(2,013,162)	(2,013,162)	
							2,410,362	2,410,362
					1	4,225,555	4,225,555	
管工				式	1	4,225,555	4,225,555	
					1	948,752	948,752	
φ75本管工事（配水支管）							(825,920)	
							2,385,640	
φ75本管工事（配水支管）							(825,920)	
							2,385,640	
材料費					1	(825,920)	(825,920)	
							825,920	825,920
φ75本管工事（配水支管）				式	1	(825,920)	(825,920)	
							825,920	825,920

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
					1	1,217,934	1,217,934	
	土工			式	1	1,217,934	1,217,934	
					1	341,786	341,786	
	管工			式	1	341,786	341,786	
							(438,152)	
							1,700,536	
φ50本管工事(配水支管)							(461,142)	
							1,744,979	
					1	(438,152) 676,472	(438,152) 676,472	
	材料費			式	1	(461,142) 699,462	(461,142) 699,462	
					1	812,906	812,906	
	土工			式	1	827,485	827,485	
					1	211,158	211,158	
	管工			式	1	218,032	218,032	
							(794,460)	
							1,381,412	
φ150消火栓設置工事(配水支管)							(809,126)	
							1,398,914	
					1	(794,460) 1,334,130	(794,460) 1,334,130	
	材料費			式	1	(809,126) 1,348,796	(809,126) 1,348,796	
					1	47,282	47,282	
	管工			式	1	50,118	50,118	
							(600,020)	
							990,373	
φ100消火栓設置工事(配水支管)							(600,020)	
							990,373	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
	材料費				1	(600,020) 959,800	(600,020) 959,800	
				式	1	(600,020) 959,800	(600,020) 959,800	
	管工				1	30,573	30,573	
				式	1	30,573	30,573	
給水管接合替工事（配水支管）							(3,351,415) 7,712,788	
							(3,469,598) 7,762,341	
	材料費				1	(230,430) 309,870	(230,430) 309,870	
				式	1	(240,740) 320,180	(240,740) 320,180	
	土工				1	1,680,764	1,680,764	
				式	1	1,677,720	1,677,720	
	管工				1	(3,120,985) 5,722,154	(3,120,985) 5,722,154	
				式	1	(3,228,858) 5,764,441	(3,228,858) 5,764,441	
仮設給水替工事（配水支管）							(4,366,097) 12,777,279	
							(4,765,756) 13,307,829	
	材料費				0	0 0	0 0	
				式	1	(119,970) 119,970	(119,970) 119,970	
	土工				1	4,860,942	4,860,942	
				式	1	4,913,407	4,913,407	
	管工				1	(4,366,097) 7,916,337	(4,366,097) 7,916,337	
				式	1	(4,645,786) 8,274,452	(4,645,786) 8,274,452	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別/規格	単位	数量	単価	金額	摘要
φ150本管撤去工事（配水支管）							-81,255	
							-81,255	
	管工				1	350,491	350,491	
				式	1	350,491	350,491	
	現場発生品				1	-431,746	-431,746	
				式	1	-431,746	-431,746	
φ100本管撤去工事（配水支管）							1,177,629	
							1,177,629	
	土工				1	891,801	891,801	
				式	1	891,801	891,801	
	管工				1	285,828	285,828	
				式	1	285,828	285,828	
φ75本管撤去工事（配水支管）							110,564	
							110,564	
	管工				1	110,564	110,564	
				式	1	110,564	110,564	
φ50本管撤去工事（配水支管）							35,091	
							35,091	
	管工				1	35,091	35,091	
				式	1	35,091	35,091	

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事等

費 目	工 種	種 別	細別／規格	単 位	数 量	単 価	金 額	摘 要
直接工事費					1		(15,620,036)	
				式	1		63,268,056	
共通仮設費					1		(16,188,464)	
				式	1		65,040,574	
共通仮設費					1		5,922,196	
				式	1		6,038,979	
共通仮設費率計算額					1		5,820,000	
				式	1		5,936,000	
共通仮設費 積上額計					1		102,196	
				式	1		102,979	
運搬費					1		16,356	
				式	1		17,139	
運搬費			運搬費		1		16,356	
				式	1		17,139	
技術管理費					1		85,840	
				式	1		85,840	
土質試験			土質試験 土質区分判定のための調査試験		1		85,840	
				式	1		85,840	
純工事費					1		69,190,252	
				式	1		71,079,553	
現場管理費					1		20,008,000	
				式	1		20,452,000	

