

變更設計書

施工年度：令和7年度	起案日	令和 年 月 日	決裁日	令和 年 月 日
	決裁根拠： 条 項 号 別表第1 3(3)表20項		書類名： 建設改良工事・委託関係綴	

• • • • •

$$\vdots$$
枚方市上下水道局

工 事 概 要

建設改良費（配水支管）

種 別	形 質	単位	当初	変更
布設工	P E ϕ 1 0 0	m	2 3 3 . 7	2 2 4 . 0
	P E ϕ 7 5	m	1 9 3 . 9	1 7 0 . 7
	P E ϕ 5 0	m	2 1 1 . 5	1 7 7 . 6
設置工	仕切弁 ϕ 1 0 0	箇所	8	8
	仕切弁 ϕ 7 5	箇所	1 0	1 3
	仕切弁 ϕ 5 0	箇所	1	2
	消火栓 ϕ 7 5	箇所	2	2
撤去工	C I P ϕ 1 0 0	m	2 2 1	2 2 1
	D I P ϕ 1 0 0	m	6	6
	C I P ϕ 7 5	m	1 2 9	1 2 9
	D I P ϕ 7 5	m	3 1	3 1
	V P ϕ 5 0	m	1 6 4	1 6 4
	H I V P ϕ 4 0	m	2 2	2 2
給水管接合替工		箇所	9 3	9 2
仮設給水替工		式	1	1
付帯工		式	1	1

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費 目	工 種	種 別	細別／規格	単位	数 量	単 価	金 額	摘 要
φ 100本管工事（更新）							(2,874,650)	
							8,047,362	
							(2,775,110)	
							7,861,798	
	材料費				1	(2,874,650)	(2,874,650)	
						3,579,770	3,579,770	
				式	1	(2,775,110)	(2,775,110)	
						3,568,370	3,568,370	
	土工				1	3,574,641	3,574,641	
				式	1	3,401,749	3,401,749	
	管工				1	892,951	892,951	
				式	1	891,679	891,679	
φ 75本管工事（更新）							(1,352,560)	
							5,092,458	
							(1,667,240)	
							5,736,848	
	材料費				1	(1,352,560)	(1,352,560)	
						1,793,260	1,793,260	
				式	1	(1,667,240)	(1,667,240)	
						2,372,360	2,372,360	
	土工				1	2,747,231	2,747,231	
				式	1	2,788,369	2,788,369	
	管工				1	551,967	551,967	
				式	1	576,119	576,119	
φ 50本管工事（更新）							(1,071,480)	
							5,054,648	
							(1,096,220)	
							5,092,048	
	材料費				1	(1,071,480)	(1,071,480)	
						1,600,320	1,600,320	
				式	1	(1,096,220)	(1,096,220)	
						1,625,060	1,625,060	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別／規格	単位	数量	単価	金額	摘要
	土工				1	2,894,100	2,894,100	
				式	1	2,872,569	2,872,569	
	管工				1	560,228	560,228	
				式	1	594,419	594,419	
φ 100消火栓設置工事（更新）							(242,825) 458,684	
							(242,825) 458,684	
	材料費				1	(242,825) 442,225	(242,825) 442,225	
				式	1	(242,825) 442,225	(242,825) 442,225	
	管工				1	16,459	16,459	
				式	1	16,459	16,459	
φ 75消火栓設置工事（更新）							(212,040) 427,657	
							(212,040) 427,657	
	材料費				1	(212,040) 411,440	(212,040) 411,440	
				式	1	(212,040) 411,440	(212,040) 411,440	
	管工				1	16,217	16,217	
				式	1	16,217	16,217	
給水管接合替工事（更新）							(4,058,048) 9,527,962	
							(4,039,823) 9,799,982	
	材料費				1	(312,438) 488,718	(312,438) 488,718	
				式	1	(93,620) 93,620	(93,620) 93,620	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別／規格	単位	数量	単価	金額	摘要
	土工				1	2,196,485	2,196,485	
				式	1	2,669,797	2,669,797	
	管工				1	(3,745,610) 6,842,759	(3,745,610) 6,842,759	
				式	1	(3,946,203) 7,036,565	(3,946,203) 7,036,565	
仮設給水替工事（更新）							(2,732,430) 11,597,626	
							(2,827,636) 11,766,223	
	材料費				1	(1,061,650) 1,223,130	(1,061,650) 1,223,130	
				式	1	(1,103,550) 1,265,030	(1,103,550) 1,265,030	
	土工				1	4,938,642	4,938,642	
				式	1	4,960,018	4,960,018	
	管工				1	(1,670,780) 5,435,854	(1,670,780) 5,435,854	
				式	1	(1,724,086) 5,541,175	(1,724,086) 5,541,175	
φ100本管撤去工事（更新）							127,018	
							127,018	
	管工				1	277,042	277,042	
				式	1	277,042	277,042	
	現場発生品				1	-150,024	-150,024	
				式	1	-150,024	-150,024	
φ75本管撤去工事（更新）							147,094	
							147,094	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別／規格	単位	数量	単価	金額	摘要
	管工				1	147,094	147,094	
				式	1	147,094	147,094	
φ 50本管撤去工事（更新）							68,209	
							68,209	
	管工				1	68,209	68,209	
				式	1	68,209	68,209	
φ 40本管撤去工事（更新）							330,705	
							330,705	
	土工				1	313,334	313,334	
				式	1	313,334	313,334	
	管工				1	17,371	17,371	
				式	1	17,371	17,371	
舗装本復旧工事（更新）							9,809,750	
							9,651,681	
	土工				1	9,809,750	9,809,750	
				式	1	9,651,681	9,651,681	
仮設工							5,355,000	
							5,355,000	
	交通管理工				1	5,355,000	5,355,000	
				式	1	5,355,000	5,355,000	

直接工事費内訳書

工種：開削工事及び小口径推進工事等

費目	工種	種別	細別／規格	単位	数量	単価	金額	摘要
直接工事費計							(12,544,033)	
							56,044,173	
							(12,860,894)	
							56,822,947	

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事等

費 目	工 種	種 別	細別／規格	単位	数 量	単 価	金 額	摘 要
直接工事費					1		(12,544,033) 56,044,173	
				式	1		(12,860,894) 56,822,947	
共通仮設費					1		6,390,936	
				式	1		6,440,980	
	共通仮設費率計算額				1		5,391,000	
				式	1		5,441,000	
	共通仮設費 積上額計				1		999,936	
				式	1		999,980	
		運搬費			1		6,394	
				式	1		6,438	
			運搬費		1		6,394	
					1		6,438	
		準備費			1		993,542	
				式	1		993,542	
			試掘工 1号工/B1.0×I2.0×H1.4/2箇所		1		109,438	
					1		109,438	
			設計費 (図面作成・地下埋設物調査)		1		792,684	
				式	1		792,684	
			土質試験 土質区分判定のための調査試験/2試料		1		91,420	
				式	1		91,420	

本 工 事 内 訳 書

工種：開削工事及び小口径推進工事等

費 目	工 種	種 別	細別／規格	単位	数 量	単 価	金 額	摘 要
純工事費					1		62,435,109	
				式	1		63,263,927	
現場管理費	現場管理費				1		18,649,000	
				式	1		18,850,000	
		現場管理費率計算額			1		18,649,000	
				式	1		18,850,000	
工事原価					1		81,084,109	
				式	1		82,113,927	
	一般管理費等				1		13,955,891	
				式	1		14,106,073	
		一般管理費率計算額			1		13,927,000	
				式	1		14,083,000	
		契約保証費			1		31,654	
				式	1		31,654	
工事価格					1		95,040,000	
				式	1		96,220,000	
消費税相当額					1		9,504,000	
				式	1		9,622,000	
本工事費					1		104,544,000	
				式	1		105,842,000	